클라우드 데브옵스(DevOps) 과정 1차 팀 프로젝트 발표

내부망 서버 구축을 통한 워크 스페이스 환경 구축

과 정명: 클라우드 데브옵스 엔지니어

및 관리자 양성과정


담당교사: 박남규

교육기관: 한국정보교육원

팀 명:구직자들

팀 원:이대성 전원경 박용진 김연수






목차 A table of contents


- 프로젝트 배경 및 목적
- 2 프로젝트구성
- 3 서비스운영과정및진행모습
- 4 프로젝트진행과정&확장가능성





¹ 프로젝트 배경 및 목적

#1 프로젝트 배경



¹ 프로젝트 배경 및 목적


#2 프로젝트 목적





2 프로젝트 구성

#1 서비스 구성





² 프로젝트 구성

#2 네트워크 구성 – 가상화(Router)





Router

: ● R1 × ●	R1#sh ip int b						
1	Interface	IP-Address	OK?	Method	Status		Protocol
interface Ethernet0/0 ip address 10.0.50.1 255.0.0.0	Ethernet0/0	10.0.50.1	YES	NVRAM	up		up
<pre>ip nat outside ip virtual-reassembly in</pre>	Ethernet0/1	20.20.20.1	YES	NVRAM	up		up
ip ospf authentication-key rnwlrwk	Ethernet0/2	unassigned	YES	NVRAM	administratively	down	down
duplex auto !	Ethernet0/3	unassigned	YES	NVRAM	administratively	down	down
interface Ethernet0/1	Ethernet1/0	unassigned	YES	NVRAM	administratively	down	down
ip address 20.20.20.1 255.255.255.224 ip nat inside	Ethernet1/1	unassigned	YES	NVRAM	administratively	down	down
<pre>ip virtual-reassembly in ip ospf authentication-key rnwlrwk</pre>	Ethernet1/2	unassigned	YES	NVRAM	administratively	down	down
duplex auto	Ethernet1/3	unassigned	YES	NVRAM	administratively	down	down
!	Serial2/0	unassigned	YES	NVRAM	administratively	down	down
: • R1 × ⊕	Serial2/1	unassigned	YES	NVRAM	administratively	down	down
	Serial2/2	unassigned	YES	NVRAM	administratively	down	down
I.	Serial2/3	unassigned	YES	NVRAM	administratively		
router ospf 1	Serial3/0	unassigned	YES	NVRAM	administratively		28/1/2 - 1/4/12/
area 0 authentication	Serial3/1	unassigned		NVRAM	administratively		3.7
network 10.0.0.0 0.255.255.255 area 0	Serial3/2	unassigned		NVRAM	administratively		
network 20.20.20.0 0.0.0.31 area 0	Serial3/3	unassigned		NVRAM	administratively		
!	NVI0	10.0.50.1		unset	up		ир

² 프로젝트 구성

#2 네트워크 구성 - 가상화(L3, L2 Switch)





2 프로젝트 구성

#2 네트워크 구성 - On-Premise



Router

```
nterface GigabitEthernet0/0
 ip address dhcp
 ip nat outside
 duplex auto
speed auto
interface GigabitEthernet0/1
 ip address 10.50.50.1 255.0.0.0
 ip nat outside
 ip virtual-reassembly
 ip ospf authentication-key rnwlrwk
duplex auto
 speed auto
interface GigabitEthernet0/2
ip address 30.30.30.129 255.255.255.224
ip nat inside
 ip virtual-reassembly
ip ospf authentication-key rnwlrwk
duplex auto
 speed auto
log-adjacency-changes
area 0 authentication
network 30.30.30.0 0.0.0.255 area 0
network 211.48.72.168 0.0.0.0 area 0
ip forward-protocol nd
no ip http server
no ip http secure-server
ip nat pool test 10.0.0.0 10.255.255.255 netmask 255.0.0.0 ip nat inside source list 1 pool test overload
ip nat inside source list 2 pool test overload
ip nat inside source list 2 pool test overload ip nat inside source list 3 pool test overload ip nat inside source list 4 pool test overload ip nat inside source list 5 pool test overload ip route 0.0.0.0 0.0.0.0 10.0.0.1
access-list 1 permit 30.30.30.0 0.0.0.31
access-list 2 permit 30.30.30.32 0.0.0.31
access-list 4 permit 30.30.30.64 0.0.0.31
access-list 5 permit 30.30.30.96 0.0.0.31
```



```
switchport trunk native vlan 818
switchport mode trunk
interface FastEthernet2/0/2
 switchport trunk native vlan 818
switchport mode trunk
interface FastEthernet2/0/15
no switchport
ip address 30.30.30.130 255.255.255.224
interface FastEthernet2/0/24
switchport access vlan 40
switchport trunk encapsulation dotlq
switchport mode access
nterface GigabitEthernet2/0/1
interface GigabitEthernet2/0/2
interface Vlanl
no ip address
nterface Vlan40
ip address 30.30.30.1 255.255.255.224
nterface Vlan50
ip address 30.30.30.33 255.255.255.224
interface Vlan60
interface Vlan70
ip address 30.30.30.97 255.255.255.224
log-adjacency-changes
network 30.30.30.0 0.0.0.255 area 0
ip classless
ip route 0.0.0.0 0.0.0.0 30.30.30.129
ip route 10.0.0.0 255.0.0.0 10.0.0.1
ip route 30.0.0.0 255.0.0.0 30.30.30.129
ip route 30.0.0.0 255.0.0.0 30.30.30.128
p http server
p http secure-server
```




interface FastEthernet0/1 switchport access vlan 50 switchport mode access interface FastEthernet0/13 switchport trunk native vlan 818 switchport mode trunk interface FastEthernet0/14 switchport trunk native vlan 818 switchport mode trunk

```
interface FastEthernet0/1
switchport access vlan 60
switchport mode access
interface FastEthernet0/2
switchport access vlan 70
switchport mode access
interface FastEthernet0/13
switchport trunk native vlan 818
switchport mode trunk
interface FastEthernet0/14
switchport trunk native vlan 818
switchport mode trunk
```

2 프로젝트 구성

#3-1 시스템 구성 (가상화)



	대역대	가상 / 물리 구분	장비명	호스트 IP
Γ	20.20.20.x		라우터	0 ~ 31
		가상화	DNS	32 ~ 63
			WEB	64 ~ 95
			WAS	96 ~ 127
			DB	128 ~ 159
			L3	62, 94, 126, 158


















² 서비스 / 시스템구성


#3-2시스템구성(온-프레미스)




번호	장비명	제품회사	수량
1	HP ProLiant DL360 G7	НР	4
2	Cisco 2900 Series	CISCO	1
3	Catalyst 2960 Series	CISCO	2
4	Catalyst 3750 Series	CISCO	1


대역대	가상 / 물리 구분	장비명	호스트 IP
30.30.30.x ਣ		Server(DNS)	2
		Server(WEB)	34
	온 프레미스	Server(WAS)	86
		Server(DB)	98
		L3	1, 33, 65, 97






#1 서비스 운영 과정







#2-1 서비스 진행 모습 (회원가입)




#2-2서비스 진행 모습(로그인)



#2-3서비스 진행 모습(시연 영상)




#3서비스모니터링(Zabbix)





⁴ 프로젝트 진행 과정 & 확장 가능성

#1 프로젝트 진행 과정



4 프로젝트 진행 과정 & 확장 가능성

#1 프로젝트 진행 과정

프로젝트제목 오늘날짜			1차 프로젝트 1차 프로젝트 (1월 3일~2월 1일) [진행률: 100%]									
			02월 01일	02월 01일						총 진행률	100%	
		계획										
진행업무	담당자	결과물	이전업무(선택사항)	시작일	작업일수	경과일수	종료일	시작일	작업일수	경과일수	종료일	진행현황
요구분석 - 주제 분석 및 선정	팀장 이대성	프로젝트 계획서		1월 3일	1	1	1월 4일	1월 2일	1	1	1월 3일	100%
설계 - 토쫄로지 설계	팀원 전원경. 팀장 이대성	토폴로지 템플릿	요구분석 - 주제 분석 및 선정	1월 3일	2	2	1월 5일	1월 3일	2	2	1월 5일	100%
설계 - 인프라 연동 설계	팀장 이대성	인프라 설계 완성본	설계 - 토폴로지 설계	1월 5일	1	1	1월 6일	1월 5일	1	1	1월 6일	100%
설계 - 서비스 설계	팀원 전원경, 팀원 박용진	서비스 설계 완성본	설계 - 인프라 연동 설계	1월 6일	2	2	1월 10일	1월 6일	2	2	1월 10일	100%
구현 - On Premise	팀원 김연수, 팀원 전원경	물리 서버 구축화	설계 트폰르지 설계	1월 8일	2	2	1월 10일	1월 9일	2	2	1월 10일	100%
구현 - DNS, NTP	팀원 박용진	DNS, NTP 구현	구현 - Switch, Router	1월 10일	3	3	1월 13일	1월 10일	3	4	1월 13일	100%
구현 - WEB	팀장 이대성	JSP 회원가입, 로그인 구현	설계 - 토폴로지 설계	1월 9일	10	14	1월 23일	1월 9일	12	16	1월 25일	100%
구현 - WAS	팀원 김연수, 팀원 박용진	웹과 DB 연결	설계 - 토폴로지 설계	1월 9일	10	14	1월 23일	1월 9일	12	16	1월 25일	100%
구현 - DB	당원 박용진, 당원 강연수	DB구축 및 데이블 구현	실제 - 도플로지 실제	1월 9월	10	4	1월 23일	1월 9일	12	16	1월 25일	100%
테스트 및 디버그	팀원 전원경, 팀원 박용진	기능 테스트 확인	구현 - DNS, NTP	1월 23일	3	3	1월 26일	1월 25일	3	5	1월 30일	100%
발표자료 - PPT	팀원 김연수	PPT 발표자료	테스트 및 디버그	1월 26일	3	4	1월 31일	1월 25일	4	6	1월 31일	100%
발표준비 및 발표	팀원 김연수	발표	발표자료 - PPT	1월 30일	2	2	2월 1일	1월 30일	2	2	2월 1일	100%
결과 보고서 작성	팀장 이대성	결과 보고서	발표준비 및 발표	1월 30일	2	2	2월 1일	1월 30일	2	2	2월 1일	100%









4 프로젝트 진행 과정 & 확장 가능성

#2서비스확장가능성



QnA # feat.구직자들

001



프로젝트 계획 인프라 연동 설계 JSP Page 구현

가상화 환경 구축

002



서비스 설계

003



DNF, NTP 구현 DB 서버 구현 테스트 및 디버그 004



On-Premise 환경 구축

WAS 서버 구현

PPT 제작 및 발표

팀장 이대성

E-Mail. leeds816@gmail.com **TEL.** 010-8592-9727

팀원 전원경

E-Mail. jwk3584@naver.com TEL. 010-9092-3584

팀원 박용진

E-Mail. 0_youngjin@naver.com **TEL.** 010-4222-8892

팀원 김연수

E-Mail. dustn0176@naver.com **Tel.** 010-3599-0176

